


# RedLine® Tools

PERFORMANCE MATTERS



## Included Hardware:

1 pc RVSCR	1/4-20 x 1.25 SHCS Clamping Rod Bolt	1 pc RVSBB	1/2-13 x 1 SHCS Mounting Bracket Bolt
1 pc RVSPAB	1/4-20 x 1.75 SHCS Pivot Arm Bolt	1 pc RVSPCW	1/4" Washer for Pivot Clamp

## To Order Entire Kits:

**RVSKL100** - Vise Stop Kit - **LEFT HAND MOUNT**  
for standard 6" vise, includes all items above except RVSRB, which can be ordered separately

**RVSKR100** - Vise Stop Kit - **RIGHT HAND MOUNT**  
for Standard 6" vise includes all items above except RVSLB, which can be ordered separately

## VersaStop - Set up and Use:

Your RedLine Tools VersaStop is shipped ready to attach to your vise.

For correct installation, rest the mounting bracket square on vise ways and fasten it with the supplied 1/2-13 socket head cap screw. Insert the desired stop rod into the stop rod clamp, position to desired length and tighten the clamp to **30 in/lbs.** Warning never tighten over **40 in/lbs.**

Position the stop by loosening the pivot clamp screw. Once in position, tighten pivot clamp screw. Do not exceed **100 in/lbs.**

Your VersaStop is supplied with 1/4" diameter stop rods. Your VersaStop will accept stop rods from 1/16" to 3/8" in diameter. **Clearance issues may arise when using stop rods smaller than 1/4" diameter.** A shorter or longer bolt may need to be used when using other stop rods.

Any questions please contact us at:

RedLine Tools - 15150 25th Avenue North, Plymouth, MN 55447  
800.791.7542 • redlinetools.com • support@redlinetools.com

